

Backyard Refresh 2026

Prepared 10/1/2026 · Planning estimate · 3 calculation(s), 2 area(s) · Price not entered

Project dimensions

Area	Dimensions
Gravel area 1	20 ft × 30 ft
Patio area	12 ft × 20 ft

Calculations

Gravel Calculator — Gravel (crushed stone)

INPUTS		RESULT	
Area 1 (rectangle)	20 x 30 ft	Area	600.0 sq ft
Use case	walkway	Volume incl. waste	6.11 cu yd
Depth	3 in	Recommended order	6.25 cu yd
Waste allowance	10 %	Estimated weight	8.56 tons
Truck capacity	10 tons	0.5 cu ft bags	330 bags
		Truckloads	1 loads

ORDER QUANTITIES

Area	600 sq ft
Cubic yards	6.25 cubic yards
Tons	8.56 tons
0.5 cu ft bags	330 bags
Truckloads	1 load

Waste allowance applied: 10%

Fence Calculator — Fence Project

INPUTS

Fence length	100 ft
Fence height	6 ft
Post spacing	8 ft
End posts	2
Gates	1
Gate width	4 ft
Waste allowance	10 %
Picket width	5.5 in
Picket spacing	0.13 in
Panel width	8 ft
Rails per section	2
Rail stock length	8 ft
Post-hole diameter	12 in
Post-hole depth	30 in
Fasteners per picket per rail	2
Fasteners per panel	8

RESULT

Net fence run	96.00 ft
Posts	15 posts
Rails	27 pieces
Pickets	226 pickets
Post-hole concrete	1.25 cu yd
Fasteners	995 each

ORDER QUANTITIES

Total posts	15 posts
Rails	27 rails
Pickets	226 pickets
Post-hole concrete	1.25 cubic yards
Hardware	995 each

Waste allowance applied: 10%

Deck Material Calculator — Deck Project

INPUTS		RESULT	
Deck length	20 ft	Area	600.0 sq ft
Deck width	30 ft	Decking boards	142 pieces
Decking board width	5.5 in	Decking linear ft	2272.00 linear ft
Decking stock length	16 ft	Joists	27 pieces
Board gap	0.13 in	Fasteners	6759 each
Board run direction	length		
Joist spacing	16 in		
Joist width	1.5 in		
Joist depth	7.25 in		
Waste allowance	10 %		
Fasteners per board per joist	2		

ORDER QUANTITIES

Decking boards	142 pieces
Decking linear feet	2272 linear ft
Joists	27 pieces
Beams	0 pieces
Posts	0 posts
Fasteners	6759 each

Waste allowance applied: 10%

Materials

Material	Quantity	Waste
Gravel (crushed stone)	Area: 600 sq ft, Cubic yards: 6.25 cubic yards, Tons: 8.56 tons, 0.5 cu ft bags: 330 bags, Truckloads: 1 load	10%
Fence Project	Total posts: 15 posts, Rails: 27 rails, Pickets: 226 pickets, Post-hole concrete: 1.25 cubic yards, Hardware: 995 each	10%
Deck Project	Decking boards: 142 pieces, Decking linear feet: 2272 linear ft, Joists: 27 pieces, Beams: 0 pieces, Posts: 0 posts, Fasteners: 6759 each	10%

Estimated costs

Amounts print in USD United States dollar, the currency selected in the header. Prices were entered and recorded in USD; nothing here converts between currencies.

Price not entered. This plan contains quantities only — the project never invents a market price.

Shopping list

Item	Quantity
☐ Gravel (crushed stone) — Cubic yards	6.25 cubic yards
☐ Gravel (crushed stone) — 0.5 cu ft bags	330 bags
☐ Gravel (crushed stone) — Truckloads	1 load
☐ Fence Project — Total posts	15 posts
☐ Fence Project — Rails	27 rails
☐ Fence Project — Pickets	226 pickets
☐ Fence Project — Post-hole concrete	1.25 cubic yards
☐ Fence Project — Hardware	995 each
☐ Deck Project — Decking boards	142 pieces
☐ Deck Project — Joists	27 pieces
☐ Deck Project — Fasteners	6759 each

Assumptions

Assumption	Value
Waste allowance	10 %
Compaction factor	1 ×
Density used	1.4 tons/cu yd
Waste allowance	10 %
Rails per section	2
Required rail length	192 ft
Waste allowance	10 %
Decking board width	5.5 in
Decking stock length	16 ft
Board gap	0.125 in
Joist spacing	16 in

Method and limitations

Calculations are planning estimates. Verify dimensions, product yields, material densities, supplier quantities, site conditions and applicable local requirements before purchasing or building.

Quantities include each calculator's waste, compaction and rounding assumptions, which are listed above. They are planning estimates for ordering material — not structural engineering, site surveying, drainage design, code compliance or a substitute for manufacturer instructions.